# Connection Strength Evaluation of the EP Henry Cast Stone Wall System and Tencate Mirafi 2XT Geosynthetic Soil Reinforcement

for

EP Henry Corporation PO Box 615 Woodbury, NJ 08096

> Project No. 14-539-1 Date: March 19, 2015

## Conducted by:





### RESEARCH AND DEVELOPMENT LABORATORY

The NCMA Research and Development Laboratory is devoted to the scientific research and testing of concrete masonry products and systems. The Laboratory is staffed by professional engineers and technicians with many years of experience in the concrete masonry industry. The Laboratory is equipped to perform nearly any physical research or testing of concrete masonry units and assemblages. The Laboratory performs research and development work for both the Association and individual companies.

### NATIONAL CONCRETE MASONRY ASSOCIATION

The National Concrete Masonry Association (NCMA) is a non-profit organization whose mission is to support and advance the common interests of its members in the manufacture, marketing, research, and application of concrete masonry products. The Association is an industry leader in providing technical assistance and education, marketing, research and development, and product and system innovation to its members and to the industry.

Research and Development Laboratory Staff
Dominick O. Dowds, P.E., Manager, Research and Development Laboratory
Douglas H. Ross, Laboratory Supervisor
Cory McGrath, Laboratory Technician
Henry Tarring, Laboratory Technician

NCMA Technical Staff

Jason J. Thompson, *Vice President of Engineering*Dennis W. Graber, P.E., *Director of Technical Publications*Nicholas R. Lang, P.E., *Director of Research and Development*Gabriela Mariscal, *Geotechnical Engineer* 

National Concrete Masonry Association Research and Development Laboratory 13750 Sunrise Valley Drive Herndon, Virginia 20171 (703) 713-1900 www.ncma.org

THIS PUBLICATION IS INTENDED FOR USE BY PROFESSIONAL PERSONNEL COMPETENT TO EVALUATE THE SIGNIFICANCE AND LIMITATIONS OF THE INFORMATION PROVIDED HEREIN, AND WILLING TO ACCEPT TOTAL RESPONSIBILITY FOR THE APPLICATION OF THIS INFORMATION IN SPECIFIC INSTANCES. RESULTS FROM TESTS MAY VARY AND THE NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA) DOES NOT WARRANT THE RESULTS CONTAINED HEREIN FOR SPECIFIC USES OR PURPOSES AND THE FINDINGS ARE NOT A SUBSTITUTE FOR SOUND ENGINEERING EVALUATIONS, JUDGMENT AND OPINIONS FOR SPECIFIC PROJECTS OR USES. THE NCMA IS NOT RESPONSIBLE FOR THE USE OR APPLICATION OF THE INFORMATION CONTAINED IN THIS PUBLICATION AND DISCLAIMS ALL RESPONSIBILITY THEREFORE.

Connection Strength Evaluation of the EP Henry Cast Stone Wall System and Tencate Mirafi 2XT Geosynthetic Soil Reinforcement For: EP Henry Corporation The measured and calculated values provided in this report are the official values resulting from this body of work. Values in parenthesis are mathematical conversions provided for reference only and may differ slightly from the official values due to conversion rounding.

This report was prepared for EP Henry Corporation by the National Concrete Masonry Association Research and Development Laboratory based upon testing, analyses, or observations performed by the National Concrete Masonry Association Research and Development Laboratory. Reference herein to any specific commercial product, process, or service by trade name, trademark, or manufacturer does not necessarily constitute or imply its endorsement or recommendation by the National Concrete Masonry Association or its staff. The contents of this report have been reviewed by the following individuals, who believe to the best of their ability that the observations, results, and conclusions presented in this report are an accurate and true representation of the services provided.

The NCMA Research and Development Laboratory is accredited in accordance with the recognized International Standard ISO/IEC 17025:2005. This accreditation demonstrates technical competence for a defined scope and the operation of a laboratory quality management system (refer to the joint ISO-ILAC-IAF Communiqué dated 18 June 2005). All test results presented here, except as noted below, are within the scope of accreditation for the NCMA Research and Development Laboratory.

Results for ultimate strength of geosynthetic reinforcement in accordance with ASTM D6637 were provided by the manufacturer. These results have not been evaluated by the NCMA Research and Development Laboratory nor are they covered in the Laboratory's scope of accreditation.

Jominick Jourds

3/19/2015

Dominick O. Dowds, Manager, Research and Development Laboratory

Date

Nicholas R. Lang, Director of Research and Development

Date

3/19/2015

This report shall not be reproduced, except in full, without the written authorization of the National Concrete Masonry Association Research and Development Laboratory.

Page 3 of 13 Project Number 14-539-1 March 19, 2015

For: EP Henry Corporation

# TABLE OF CONTENTS

1.0 INTRODUCTION	5
2.0 MATERIALS	5
3.0 CONNECTION STRENGTH PROCEDURES	7
4.0 RESULTS	9
5.0 DISCUSSION	10
6.0 REFERENCES	10
APPENDIX A – MIRAFI 2XT RESULTS	12

# Connection Strength Evaluation of the EP Henry Cast Stone Wall System and Tencate Mirafi 2XT Geosynthetic Soil Reinforcement

### 1.0 INTRODUCTION

The connection strength between a geosynthetic reinforcement and segmental retaining wall (SRW) unit is a design component of any mechanically stabilized earth system. This connection strength is determined through testing in accordance with ASTM D6638-11, Standard Test Method for Determining Connection Strength Between Geosynthetic Reinforcement and Segmental Concrete Units (Modular Concrete Block) (Ref. 1). In this project, the connection strength of the EP Henry Cast Stone Wall System with Tencate Mirafi 2XT geosynthetic was evaluated, the results of which are reported herein.

### 2.0 MATERIALS


All SRW units and geosynthetic reinforcement were sampled and provided by the client. The SRW units are dry-cast concrete blocks and part of the system with the trade name 'EP Henry Cast Stone Wall System'. Figure 1 shows the configuration of these units. Table 1 provides the representative dimensions of the units determined by the Laboratory as applicable to this testing program. At the direction of the client, testing for other unit physical properties, such as compressive strength and absorption, were not determined as part of this project.



Figure 1 – Representative SRW Unit

Table 1 – Representative SRW Unit Physical Properties								
Length front of unit, in. (mm)	16.0 (406)							
Length back of unit, in. (mm)	10.5 (267)							
Height, in. (mm)	6.0 (152)							
Width, in. (mm)	11.5 (292)							
Received weight, lb (kg)	48.18 (21.85)							

For connection strength testing the cores and spaces between the SRW units were filled with aggregate. The gradation of the aggregate was determined in accordance with ASTM C136-06, *Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates* (Ref. 2). Figure 2 shows the gradation of the aggregate used. The aggregate was consolidated into the cells and voids of the SRW assemblies by rodding.



Note – to convert sieve size to inch, divide by 25.4.

For: EP Henry Corporation

Figure 2 – Aggregate Gradation

The connection strength was determined using geosynthetic reinforcement with the trade name "Mirafi 2XT", manufactured by Tencate Geosynthetics. This geosynthetic is constructed out of high molecular weight and high tenacity polyester yarns utilizing a complex knitting process and a polymeric coating. The manufacturer's website (<a href="www.geogrid.com">www.geogrid.com</a>) contains published information for the ultimate tensile strength of the geosynthetic materials used in this project. As provided by the manufacturer the ultimate tensile strength reportedly obtained when tested in accordance with ASTM D6637 (2010), Standard Test Method for Determining Tensile Properties of Geogrids by the Single or Multi Rib Tensile Method (Ref. 3), is 2,000 lb/ft (29.2 kN/m) for this geosynthetic.

### 3.0 CONNECTION STRENGTH PROCEDURES

The connection strength tests were performed in accordance with ASTM D6638-11. All tests were performed with the same configuration. The testing configuration is described below and accompanying photographs are provided below.

- The bottom course was constructed using the SRW units as shown in Figure 3 and aggregate was added to the cores of the units and spaces between the units as needed.
- A 36.0 in. (914 mm) piece of geosynthetic reinforcement was placed on top of the units so that it would meet the edge of the bottom course units (Figure 4).
- A course of SRW units was placed on top of the lower course of units and the geosynthetic reinforcement. The top units were place so there was no setback between the bottom and the top courses. The cores of the units and spaces between the units were filled with aggregate (Figure 5).
- A neoprene pad, steel plates, and a steel beam were placed on the top course of units to provide uniform axial load distribution (Figure 6).
- From the rear of the frame, the geosynthetic was rolled around a steel spreader bar to connect to the hydraulic rams. An aluminum frame was connected to the geosynthetic, which in turn was used to attach two linear displacement potentiometers to measure the amount of geosynthetic pullout and deformation during testing.
- The overall nominal length of the tested configuration was 4.0 ft. (1.22 m).



Figure 3 – Lower Units




Figure 4 – Placement of Geosynthetic



Figure 5 – Top Course of Units



Figure 6 – Placement of Neoprene Pad, Steel Plates, and Steel Beam



Figure 7 – Rear of Testing Setup

Once the test specimen was constructed it was tested using the procedures defined by ASTM D6638-11:

- Normal load was applied to the wall specimen through a dual ram hydraulic loading system
  applied to the steel beam, plates, and neoprene pad. The magnitude of the normal load for each
  hydraulic ram was maintained at a constant level and monitored using electronic load cells and a
  data acquisition system.
- With the normal load applied, the geosynthetic was subjected to a horizontal load by displacing the geosynthetic at a rate equal to 10% of the initial free length of grid per minute using a dual ram hydraulic load system and steel spreader bar. The free length of grid is defined as the distance from the back of the units to the loading clamp, and is 10 in. (254 mm) for this test setup. The displacement rate was 1.0 in./min (25.4 mm/min). The test was continued until the connection strength began to decrease.
- Horizontal displacement of the geosynthetic was recorded during testing.

Testing was performed at five unique normal load levels. One normal load was repeated twice, for a total of seven unique connection strength tests.

### 4.0 RESULTS

Connection strength is defined as the connection load divided by the test width of the geosynthetic reinforcement. The peak connection strength is defined as the highest recorded value of connection strength. Currently, the NCMA *Design Manual for Segmental Retaining Wall Units, Third Edition* (Ref. 4) does not include any recommendations for serviceability connection strength, nor is this value required by the design provisions within that manual. In this project, however, the connection strength at 19 mm (0.75 in.) horizontal displacement, as measured from the back of the unit, is defined as the serviceability connection strength, as this value has been historically used and was previously recommended by the NCMA *Design Manual for Segmental Retaining Wall Units, Second Edition* (Ref. 5).

Results for the connection strength testing are provided in the appendix and are summarized in Table 2. In addition to the data presented, a plot of connection strength vs. displacement as well as connection strength vs. normal load is also provided in the appendix.

As required by the test method, one axial load level was tested three times to determine repeatability. The axial load repeated was 630 lb/ft (9.2 kN/m), and the results of those tests were within the general range of repeatability of the test method ( $\pm$  10% from the mean of the three tests for the peak connection strength).

All specimens failed due to rupture of the geosynthetic reinforcement in combination with some geosynthetic displacement. Figure 8 shows a geosynthetic rupture failure typical for this project.

	Table 2 – Summary of Connection Strength Tests									
Test	Average Axial	Approximate Wall Height based on	Service State Connection	Peak Connection						
Number	Load	Axial Load	Strength	Strength						
	lb/ft (kN/m)	ft (m)	lb/ft (kN/m)	lb/ft (kN/m)						
1	258 (3.8)	2.7 (0.83)	637 (9.3)	1,150 (16.8)						
2	625 (9.1)	6.6 (2.02)	1,022 (14.9)	1,370 (20.0)						
3	440 (6.4)	4.7 (1.42)	766 (11.2)	1,293 (18.9)						
4	628 (9.2)	6.7 (2.03)	851 (12.4)	1,417 (20.7)						
5	813 (11.9)	8.6 (2.63)	1,062 (15.5)	1,587 (23.2)						
6	630 (9.2)	6.7 (2.04)	825 (12.0)	1,303 (19.0)						
7	1,005 (14.7)	10.7 (3.25)	1,233 (18.0)	1,733 (25.3)						



Figure 8 – Typical Failure Mode

### **5.0 DISCUSSION**

The following discussion is not a required portion of the ASTM D6638-11 standard, but is provided for the reference and convenience of the reader.

A plot of normal load versus connection strength is also provided in the appendix. As can be seen from this figure, a relationship can be determined for both the serviceability connection strength (at 0.75 in. [19 mm] displacement) as well as the peak connection strength as a function of normal load. Using best-fit linear trend lines, relationships are determined in accordance with the NCMA *Design Manual for Segmental Retaining Walls* (Ref. 4). As noted before, the third edition of this design manual does not include provisions for the serviceability connection strength. While ASTM D6638-11 requires that serviceability connection strength be determined, it does not define the specified displacement, leaving this displacement to be prescribed by the user. A value of 0.75 in. (19 mm) is reported here as this value has been used historically. Relationships are provided for both the peak connection strength (T<sub>cl</sub>) as well as the service state connection strength (T<sub>cw</sub>) within the range of normal load tested in this study.

These relationships apply to the combination of SRW units, geosynthetic reinforcement, and aggregate used in this study.

### 6.0 REFERENCES

- 1. ASTM Standard D6638, 2011, "Standard Test Method for Determining Connection Strength Between Geosynthetic Reinforcement and Segmental Concrete Units (Modular Concrete Block)", ASTM International, West Conshohocken, PA, www.astm.org.
- 2. ASTM Standard C136, 2006, "Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates", ASTM International, West Conshohocken, PA, www.astm.org.

- 3. ASTM Standard D6637, 2010, "Standard Test Method for Determining Tensile Properties of Geogrids by the Single or Multi-Rib Tensile Method", ASTM International, West Conshohocken, PA, www.astm.org.
- 4. NCMA Design Manual for Segmental Retaining Walls, Third Edition, 2009, National Concrete Masonry Association, 13750 Sunrise Valley Drive, Herndon, VA 20171-4662.
- 5. NCMA Design Manual for Segmental Retaining Walls, Second Edition, Third Printing, 2002, National Concrete Masonry Association, 13750 Sunrise Valley Drive, Herndon, VA 20171-4662.

For: EP Henry Corporation


Page 11 of 13 Project Number 14-539-1 March 19, 2015

Test Set EP Henry Cast Stone Wall System / Miragrid 2XT Geosynthetic

NCMA Job Number 14-539-1A

Segmental Retaining Wall Units - EP Henry Cast Stone Wall System Geosynthetic - Miragrid 2XT (Ultimate Tensile Strength, Tindex (ASTM D6687)) = 2,000 lb/ft

			Ę		ı						
		Peak	Displacemen	(in.)	2.26	1.68	2.34	1.92	1.55	1.85	1.77
	Peak	Connection	Strength	(lb/ft)	1150	1370	1293	1417	1587	1303	1733
		Peak	Tensile	Load (lb)	3450	4110	3880	4250	4760	3910	5200
		Service State	Displacement	(in.)	92'0	0.75	0.75	0.76	0.75	0.75	0.75
Service	State	Connection	Strength	(lb/ft)	637	1022	992	851	1062	825	1233
	Tensile Load at	Service State	Deformation <sup>1</sup>	(lb)	1910	3070	2300	2550	3190	2470	3700
			Slack	Tension (lb)	110	190	190	170	190	180	150
Approximate Wall	Height	Corresponding to	Applied Axial	Load (ft)	2.7	9.9	4.7	6.7	8.6	6.7	10.7
	Average	Axial	Load	(Ib/ft)	258	625	440	628	813	630	1005
		Average	Axial	Load (lb)	1030	2500	1760	2510	3250	2520	4020
			Geosynthetic	Width (ft)	3.0	3.0	3.0	3.0	3.0	3.0	3.0
		Test	Series	Number	1	2	က	4	2	9	7



1200

The following relationships are not required by D6638-11, but are provided for reference. Using best fit linear trend lines, the following relationships have been determined using the methodology found in the NCMA Design Manual for Segmental Retaining Walls (Ref. 4 and 5): Peak Connection Strength, Tcl, (lb/tt) = Normal Load \* tan 38.0° + 917 lb/tt

Service State Connection Strength, Tcw (lb/ft) = Normal Load \* tan 38.7° + 414 lb/ft


Connection Strength Evaluation of the EP Henry Cast Stone Wall System and Tencate Mirafi 2XT Geosynthetic Soil Reinforcement For: EP Henry Corporation

Test Set EP Henry Cast Stone Wall System / Miragrid 2XT Geosynthetic

Segmental Retaining Wall Units - EP Henry Cast Stone Wall System Geosynthetic - Miragrid 2XT (Ultimate Tensile Strength, Tindex (ASTM D6687)) = 29.2 kN/m

				ī						
	Peak	Displacement	(mm)	57.3	42.7	59.4	48.6	39.4	47.0	45.0
<del>.</del>	Peak Connection	Strength	(kN/m)	16.8	20.0	18.9	20.7	23.2	19.0	25.3
	Peak	Tensile	Load (kN)	15.3	18.3	17.3	18.9	21.2	17.4	23.1
	Service State	Displacement	(mm)			19.1				
Service	State	Strength	(kN/m)	9.3	14.9	11.2	12.4	15.5	12.0	18.0
Topcilo Lond at	Service State	Deformation <sup>1</sup>	(kN)	8.5	13.7	10.2	11.3	14.2	11.0	16.5
		Slack	Tension (kN)	0.5	0.8	0.8	0.8	0.8	0.8	0.7
Approximate Wall	Corresponding to	Applied Axial	Load (m)	0.83	2.02	1.42	2.03	2.63	2.04	3.25
,	Average Axial	Load	(kN/m)	3.8	9.1	6.4	9.5	11.9	9.5	14.7
	Average	Axial	Load (kN)	4.6	11.1	7.8	11.2	14.5	11.2	17.9
		Geosynthetic	Width (m)	0.91	0.91	0.91	0.91	0.91	0.91	0.91
	Test	Series	Number	1	2	က	4	2	9	7

- Service State Displacement defined as the connection strength at 19 mm displacement as recommended by the NCMA Design Manual for Segmental Retaining Wall Units (Ref. 5)



20.0

15.0

Peak

y = 0.80x + 6.03

The following relationships are not required by D6638-11, but are provided for reference. Using best fit linear trend lines, the following relationships have been determined using the methodology found in the NCMA Design Manual for Segmental Retaining Walls (Ref. 4 and 5): Peak Connection Strength, Tcl,  $(kN/m) = Normal Load * tan 38.0^\circ + 13.4 kN/m$ 

Service State Connection Strength, Tcw (kN/m) = Normal Load \* tan 38.7° + 6.0 kN/m